

QUESTION AND ANSWERS FOR:

18-34, DUE 8/1/2018

RFB FOR GAS FIRED WATER HEATER INSTALLATION

1. They only show 1" Rigid Coated RMC conduit underground run for temp indication from heater to Scada RTU Building, No cable needed only Rigid conduit, Seals at RTU Building?

Conduit only, GUC will install wire and seals.

2. They show 1/2" SS tubing for below grade feeding Heater with supply gas from Kimray connection, should all tubing fittings be 1/2" NPT?

All Tubing and Fittings shall be 1/2" NPT, unless otherwise noted.