



ADDENDUM NO. 1

FEBRUARY 26, 2015

**GREENVILLE UTILITIES COMMISSION
CNG FUELING FACILITY (GCP-91)
RIVERS & ASSOCIATES DRAWING #: W-3587**

A. SCOPE

This Addendum No. 1 consists of pages AD1-1 through AD1-2.

BIDDERS are hereby notified of the following changes in the specifications and/or drawings.

B. SPECIFICATIONS

1. Section 010100 – PROJECT REQUIREMENTS

On Page 010100-3, LINES AND GRADES, delete the second and third paragraphs and insert the following:

Basic horizontal and vertical control points have been established or designated by ENGINEER on the Drawings. These points shall be used as datum for the Work. All additional field survey, layout and measurement Work shall be performed by CONTRACTOR as a part of the Work.

CONTRACTOR shall provide an experienced surveyor, instrument man, competent assistants and such instruments, tools, stakes and other materials required to complete the survey, layout and measurement Work. In addition, CONTRACTOR shall furnish, without charge, competent surveyors from his force and such tools, stakes and other materials as ENGINEER may require in establishing or designating control points, in establishing construction easement boundaries or in checking survey, layout and measurement Work performed by CONTRACTOR.

CONTRACTOR shall keep ENGINEER informed, a reasonable time in advance, of the times and places at which he wishes to do Work, so that any checking deemed necessary by ENGINEER may be done with minimum inconvenience to ENGINEER and minimum delay to CONTRACTOR.

ADDENDUM NO. 1
FEBRUARY 26, 2015
GREENVILLE UTILITIES COMMISSION
CNG FUELING STATION (GCP-91)
RIVERS & ASSOCIATES DRAWING #: W-3587

2. Section 014000 – QUALITY CONTROL

On Page 014000-1, Testing Laboratory Services for Field Quality Control: replace this paragraph with the following:

All charges of testing laboratories for field quality control tests made in the field or laboratory on concrete, asphalt mixtures, moisture-density (Proctor) and relative density tests on embedment, fill, and backfill materials, in-place field density tests on embedments and fills, and other materials and equipment, during and after their incorporation in the Work shall be paid by Owner. Testing due to failed tests will be paid for by the Contractor. Field sampling and testing will be performed by testing-laboratory personnel, in the general manner indicated in the specifications, with minimum interference with construction operations. Engineer shall determine the exact time and location of field sampling and testing, and may require such additional sampling and testing as necessary to determine that materials and equipment conform with data previously furnished by Contractor and with the Contract Documents.

C. DRAWINGS

1. Sheet C-1, "Work by Jones & Frank"

All bollards on the site will be installed by Jones & Frank (31 total).

2. Sheet C-4, "Standard Curb & Gutter"

All curb and gutter on this project shall be 2'-0".

D. GENERAL

A Pre-Bid Conference was held on Tuesday, February 24, 2015 the minutes from that meeting are made part of this addendum by reference.

This Addendum No. 1 is submitted this 26th day of February 2015. Each BIDDER is requested to acknowledge receipt of this Addendum in the space provided in the Bid Form.

Greenville Utilities Commission
Carl H. Smith, E.I. , Gas Distribution Engineer
801 Mumford Road
Greenville, North Carolina 27834