

**QUESTION AND ANSWERS III FOR:**

**RFP # 16-51, For Old Creek Road Natural Gas Main Replacement 11/9/16**

1. Will the contractor be responsible for the tapping of the 8" Mueller Bottom Out? **Yes, the Contractor will be responsible for welding on and completion of the bottom out fitting.**
2. Can the entire project be bored? **Yes, the Contractor would be allowed to bore the entire project; however, it would have to be installed at the depths specified on the plans and specifications. The Contractor would insert his HDD price in both Line Items 3 and 4.**
3. Contractor to provide the concrete block for under the vales and valve boxes? **Greenville Utilities Commission will provide the concrete blocks for the valves and boxes.**
4. Is there a different unit price sheet, the original unit sheet has mobilization on it? **Refer to Technical Specification Section 3.2 Mobilization.**