



Water Treatment Plant Phase 1 Upgrades CMAR Selection Pre-Submittal Meeting

October 12, 2017




Water Treatment Plant Phase 1 Upgrades

- 22 mgd WTP
- Expand capacity to 32 mgd
- Upgrades to most processes
 - Only minor improvements to ozone, PI, and lagoon




Facility Expansion Site Layout



Raw Water Intake

- Intake screens will require repair or replacement to resolve recent failures
- Hazen conducting further investigations
- Construction may require temporary pumping systems and cofferdams around the screens







Raw Water Pump Station

- Upsize intake piping and pump discharge header to 42-inch
- Raw Water Pumps
 - Impeller retrofit - No. 1, 3, and 4
 - Replace Motor - No. 4
 - Install vortex suppression
- Install parallel RW pipelines to PI and bypass to WTP
 - ~2,000 ft of 30-inch
 - ~1,600 ft of 48-inch
 - (PI to Rapid Mix)





Modifications to Existing PI

- Raise outlet structure in Pre-Sedimentation Impoundment to expand supply range and provide the ability to draw from a range of water quality zones.




WTP Upgrades – Enlarged Plan

 = Phase 1



Raw Water Contactor

- 56,000 Gallon Raw Water Contactor
 - Provides sufficient sodium permanganate contact time
- Designed to accommodate future use as Pre-ozonation contactor





Coagulation and Sedimentation


- Existing
 - Increase raw water venturi meter and flow control valve size
 - Install finger weirs in the existing sedimentation basins
- New Train
 - New vertical rapid mix facility (single stage) with parallel basins. 2 basins expandable to 3 in the future
 - New 10-mgd SuperPulsator basin




Coagulation, Flocculation, and Clarification



SuperPulsator



SuperPulsator



Ozone Improvements

- Replace Gas Flowmeters (GOX meters)
- Add O₃ monitoring to off-gas to monitor transfer efficiency




Filter Upgrades & Backwash Supply Line

- 4 new single cell filters (544 sf)
- Install new BW supply header in filter gallery
- Backup Backwash Supply
 - Install PRV on backwash line from high service pump header



New Filters






New Clearwell Pump Station

- New facility at NW Corner of WTP site
- 3 new clearwell pumps drawing from a wet well
- 54-inch transmission suction piping from new filters to CWPS
- 36-inch discharge piping from CWPS to Ground Storage Tanks



FW Storage Improvements

- Modify existing tanks with curtain baffling
- Install 1 new 3-MG clearwell tank with Inset-C shotcrete baffling
- New 36-inch yard piping to HS Pump Station
- New 24-inch Clearwell drain piping




High Service Pump Station Upgrades


- Finished Water Pumps
 - Impeller retrofit and motor upgrade – No. 4
- Install vortex suppression
- Implement suction piping improvements




Improvements to Chemical Bulk Storage




New Chemical Bulk Storage Building



New Chemical Bulk Storage Building




Improvements to Existing Chemical Feed



New Pre-Chemical Feed Facility

Adjacent to SuperPulsators



RAPID MIX CHEMICAL BUILDING PLAN
3/16" = 1'-0"

PHASE 1 WTP IMPROVEMENTS
GREENVILLE UTILITIES COMMISSION



Residuals Management Improvements

- Construction of parallel 16-inch pipeline to lagoon
- Improvements to redistribute solids into lagoon
- Addition of road to lagoon for dewatering equipment access



Architectural Upgrades

- Break Room: new finishes and casework
- Lab: Minor changes to layout, new finishes and casework
- Control Room: modify layout
- Expand women's restrooms on 1st and 2nd floor
- Add Operations Supervisor Office and Storage in Filter Gallery



Electrical Upgrades

- New electrical power distribution - medium voltage primary loop to new facilities
 - Pre-Chemical Facility
 - Clearwell Pump Station
- Install 4th electrical utility transformer
- Electrical modifications to provide redundancy in key areas



QUESTIONS

