

GREENVILLE UTILITIES COMMISSION

QUESTIONS AND ANSWERS II FOR 25-67

RFB FOR BOVIET SUBSTATION STRUCTURES, EQUIPMENT & FOUNDATION DESIGN

11/13/2025 @ 2:00 PM

1. It looks like there are some PTs and CTs on a structure next to the URD stands (see circled attached). I do not see these listed in the specs or the sample BOM. Are these being provided by GUC? If not please provide information on them ASAP?

The PTs, CTs, and metering cabinets on the metering stands will be provided by GUC. Necessary terminals and conductors shall be provided by materialman. The PTs are ABB 7525A23G05, and the CTs are ABB E923A427G02. The metering cabinet is 36" x 36" x 14" HxWxD with mounting ears spaced at 37" x 26.75" HxW.