

GREENVILLE UTILITIES COMMISSION
QUESTIONS AND ANSWERS FOR 25-69
RFB FOR U-5875 NATURAL GAS MATERIALS
11/4/2025 @ 3:00 PM

1. Is the footage 13,520 FT. on the 6" PE pipe?

Yes. The footage is based on 26 full bundles of pipe.

2. When is the material needed for the job?

Materials are required prior to Dec. 1st.

3. Under delivery it says individual releases from a blanket purchase order. Will all the material be ordered all together and shipped complete to your warehouse?

GUC reserves the right to buy all or partial of what is bid, materials shall be shipped to GUC's Warehouse located at 701 Utility Way, Greenville, NC.

4. Below where 12-14 mils of FBE externally coated is noted ... will it be OK to quote and provide 14-16 mils FBE externally coated for the pipe?

14-16 Mils FBE externally coated pipe is acceptable.