

**GREENVILLE UTILITIES COMMISSION**  
**QUESTIONS AND ANSWERS FOR 26-17**  
**BIDS FOR BOVIET SUBSTATION LABOR & CONSTRUCTION**  
**5/7/2026 @ 2:00 PM**

1. Is there an estimated start date for this project?

The site is expected to be ready for steel erection in mid-September.

2. Can GUC verify that control and power cable installation is not included in this bid?

Control, power, and fiber optic cable installation is by GUC.

3. Can GUC verify that the runs on the Conduit Plan that do not specify a conduit size are direct buried cable? If not direct buried, can GUC provide the size for those runs?

Unlabeled runs are 2" PVC. Bids shall utilize estimated quantities and per-unit pricing.

4. Is the PVC the only material contractor needs to provide?

Contractor is to provide all materials for a complete conduit system including PVC conduit, fittings, solvents and adhesives, and rigid elbows for circuit exits.

5. Is there any more information on the details for the steel structure? Appendix C shows the structure but not any details.

Fabrication drawings will be provided to successful bidder when steel engineering is completed.

6. We would like to clarify if there is a specific maximum Experience Modification Number (EMR) required for a bidder to be considered "responsible and responsive" for this project.

We follow the NCGS's, 143-129, Procedure for letting of public contracts.