GREENVILLE UTILITIES COMMISSION

QUESTIONS AND ANSWERS II FOR RFB 26-66

FOR REPLACEMENT OF 12.47 KV DISTRIBUTION STRUCTURES ALONG THE GRID PHASE 2

11/19/2026 @ 2:00 PM

1. How can I find the drawing for unit number C8?

C8 is a straight-line double deadend on crossarm. Use Dwg C6 and assembly drawing XRM-10DDE for reference.

2. I assume that all transformers will be replaced? Or will they be transferred from the removed pole? Will the units for the transformers be included in the pole top unit prices?

Only the transformers on poles that will be replaced (red, yellow, and green dots on maps). Transformers are to be returned to GUC for maintenance.