

**GUC Boviet Substaion - Estiamated Quantities**  
**Boviet Substation Site Improvements**  
**February 17, 2026**

<u>Line Item</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>
1	Clearing & Grubbing	3.4	AC
2	Silt Fence	1,125	LF
3	Geo-Grid Driveway	95	SY
4	Gravel Driveway	250	SY
5	16" DIP	60	LF
6	15" RCP	75	LF
7	18" RCP	60	LF
8	24" RCP	35	LF
9	15" FES	1	EA
10	24" FES	1	EA
11	Stormwater Pond (includes excavation, wetland plantings, erosion control and outlet device, etc)	1	LS
12	Class B Rip Rap w/ Underliner	35	TN
13	Swales	925	LF
14	Substation Yard	11,500	SY
15	Common Excavation	1	LS
16	Undercut Excation & Off Site Borrow	4,000	CY