Evans Phase 2 Pre-Bid Questions

October 28, 2026

1. When are the pole scheduled to be delivered?

- Delivery dates for steel structures to be provided by Engineering once manufacturer advises.

2. Is Greenville Utilities Commission providing materials?

- Yes.

3. Where will the poles be delivered?

- Pole delivery to Mumford Road but will accommodate with winning bidder.

4. Where will the old poles be disposed of?

- The contractor will be responsible for determining the disposal location for old poles. However, GUC will provide dumpsters for cut section of poles.

5. Will the transmission lines remain energized during distribution construction?

- GUC can de-energize transmission lines during distribution construction

6. When will the load be transferred on to the new transmission lines?

- The load will be transferred upon completion of construction.

7. Is road work restricted to the hours of 9:00 AM to 4:00 PM?

- Yes.

8. Who will be oversee construction?

- Mike McGowan will serve as the primary point of contact. Doug Boone will assist with any engineering-related questions.

9. Are there restrictions on working after hours?
- Contractors will be permitted to work after hours during time-critical phases of construction. However, engineering assistance will not be available during these hours.

10. Will the vacuum truck be required in certain areas to locate existing utilities or clean existing pole holes?
- A vacuum truck may be required for these tasks. GUC will provide a designated disposal site.

11. What backfill material is required for distribution and transmission poles?
- Dirt fill be used for distribution poles, while ABC rock will be used for transmission poles. Both materials shall be furnished by contractors.

12. Are any construction delays anticipated?
- No delays are anticipated currently.

13. Are the contractors required to pull caissons?
- Yes, the contractor is required to pull caissons if possible. If not, cut one foot below grade and bury.