

GREENVILLE UTILITIES COMMISSION
PRE-BID QUESTIONS AND ANSWERS FOR 25-53
RFB FOR HUDSON'S SUBSTATION FOUNDATION
9/23/2025 @ 2:00 PM

1. Are there any underground facilities?
 - a. There are no underground facilities installed in the substation; however all contractors are obligated to complete locate tickets before excavation can begin.
2. Are there any access restrictions?
 - a. The site will be available to the contractor when beginning construction and the contractor will be able to put their lock daisy chained in the gate.
3. Are anchor bolts provided?
 - a. Anchor bolts will be delivered on site to the contractor.
4. Are the composite oil containment panels to be installed as part of the bid?
 - a. Yes, the contractor is to install the Composolite oil-containment per manufacturer instructions referenced in the specification.
5. Is concrete testing required?
 - a. Concrete tested is to be performed per the specifications, section 1.10.
6. Are two rings included for the large piers?
 - a. Yes, AB-6 patterns are fabricated with two anchor bolt templates per pier.
7. Are oil containment materials provided?
 - a. The Composolite walls, including installation materials will be provided. The SPI oil-stop device receptacle will be provided less pipe to the outflow. Contractor to provide asphalted fiber expansion joint and sealant materials as listed in specifications.
8. Are conduits to be installed through the oil containment?
 - a. Conduits will be installed by GUC and stubbed out of the area for the oil containment.