

**GREENVILLE UTILITIES COMMISSION**

**QUESTIONS AND ANSWERS FOR TREE REMOVAL SERVICES PROPOSAL**

**SEPTEMBER 15, 2021**

- 1) Are trees along Belvoir School Rd marked with silver tags? If not what is the clearing distance from the guard rail approaching Flemming School rd.  
All trees within the utility right of way and trees labeled danger trees are marked with silver tags. Along Belvoir School Rd, there are some volunteer trees within the DOT right of way that are not marked but will need to be removed. See Note 1 highlighted in yellow on page 10 of the bid package.
- 2) Which route does the proposed line take from Mt. Pleasant substation to Belvoir School Rd? Down gravel road or direct line from substation to Belvoir School Rd?  
The transmission line will go directly from the substation to Belvoir School Rd. There is currently a distribution line that runs the same route.
- 3) Can equipment be staged in grass area at Mt. Pleasant Substation?  
Equipment can be staged at 801 Mumford Rd, Greenville, NC. Due to other project conflicts, staging at Mt. Pleasant Substation will not be available.
- 4) Is forestry mulching allowed in wooded areas?  
Forestry mulching is allowed for underbrush and small trees with a DBH less than 3". Large, mature trees will need to be cut down and hauled away. Excess mulch within the right of way should be avoided.
- 5) Are stumps to remain in yards or be removed?  
Stumps should be cut to ground level. Grinding and removal is not included.